

Tender call Notice No.04/PS GUDVELLA/23-24



Bid Identification No. 04 /PS GUDVELLA/23-24

GOVERNMENT OF ODISHA PR & DW DEPARTMENT

COVER-II (Financial Bid)

BID DOCUMENT

FOR

COMPOSITE TENDER OF BUILDING WORKS

NAME OF THE WORK:

CONSTRUCTION OF COMMUNITY HALL AT

BADANGOMUNDA

UNDER GUDVELLA BLOCK BALANGIR DISTRICT, ESTIMATE

COST-20, 00,000/- (Rupees twenty lakh) only

PANCHAYAT SAMITI OFFICE, GUDVELLA

ush
06.11.23
Block Development Officer
Gudvella

BILL OF QUANTITY

Tender inviting Authority:- Block Development Officer, Gudvela

Name of the WORK :- Construction of Community Hall at Badngomunda

Bid Identification No:-10/PS,GUDVELLA/ 2023-24

Tender call Notice No:-

PART - I (CIVIL)					
Item Sl. No	Item Description	Unit	Quantity	Estimated Rate excluding GST)	Total Amount in Rs.
1	EARTH WORK				
	Earth work in excavation of foundation trenches in ordinary soil except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away form the site with all leads and lifts. T & P shoring and shuttering if required etc. complete as directed by engineer- in charge.	Cum	76.414	211.00	16123.00
2	Filling foundation and plinth with sand	Cum	62.442	613.30	38295.00
3	R.C.C. WORK				
	i. Providing , lifting hoisting laying Reinforced cement concrete of M20 grade in column footings , as per approved designs and drawings having a munimum compressive strength (in work test) 200 Kg./ Square cm in 15cm. Cubes at 28 days after mixing and tests conducted in accordance with I.S. 416 using 12mm to 20 mm size black hard crusher broken granite stone ships of approved quality from approved quarry washed and cleaned (20mm size not to exceeds 25%) to be mixed in concrete mixture with ordinary protland cement (OPC) including noisting, lowering lying andcompacting concrete by using vibrators, watering and curing for 28 days etc.	Cum	36.063	5294.40	190930.00
4	Providing & laying plain cement concrete 1:4:8 (1 cement 4 coarse and 8 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming , watering and curing etc.	Cum	21.752	4854.70	105599.00

	Fly ash brick masonry (1:6) cement mortar				
	Fly ash brick masonay in cemnet mortar of (1.6) with portland slag cement, watering and curing etc. including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all lbaour sundries T& P required for the works etc complete in all respect as directed by the Enginner in-charge.				

5	For Foundation & Plinth	Cum	17.901	4960.60	88802.00
6	For Superstructure	Cum	32.392	4998.90	161925.00
Item Sl. No	Item Description	Unit	Quantity	Estimated Rate excluding GST)	Total Amount in Rs.
7	REINFORCEMENT				
	Cold twisted steel reinforcement for RCC work including cutting bending straightening and binding with 18swg black annealed wire and placing in position complete	Qntl	34.000	9204.90	312967.00
8	Rigid smooth centering & shuttering for RCC works including false works and dismantling the same after required times etc. complete.				
8	For Foundation and Plinth, Footing, Bases of columns, Mass concrete etc.	Sqm	55.110	234.50	12923.00
9	For RCC Beams, Columns, Girders etc.	Sqm	75.165	1021.10	76751.00
10	For RCC Lintel	Sqm	16.344	528.60	8639.00
11	For RCC Roof slab, Sunshades, Chajjas, Landing, Balconies up to 4.30 Mtr	Sqm	100.963	675.90	68241.00
12	2.5 cm thick grading concrete (1:2:2) on roof slab with 6.7mm & down grades size hard granite crusher broken chips on new work in Ground Floor	Sqm	111.057	317.80	35294.00
13	12 mm thick CP in CM(1:6) over Brickworks with cost, conveyance, & royalty etc.	Sqm	216.851	151.10	32766.00
14	16 mm thick CP in CM(1:6) over Brickworks with cost, conveyance, & royalty etc.	Sqm	143.757	216.40	31109.00
15	Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials labour T & P etc. as per direction of Engineer -In -charge. in Ground Floor	Sqm	299.093	93.40	27935.00
16	Wall Painting two coats with approved Plastic Emulsion Paint over a coat of Water Bound Wall cement Primer on Plastered Surface in Ground Floor	Sqm	299.093	156.00	46659.00
17	Weather coat two coats to walls with any approved shade including cost of materials etc. complete	Sqm	143.757	149.10	21434.00
18	Fixing verified tiles in floors on 25mm thick bed of CM(1:4) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing	Sqm	76.394	1122.50	85752.00
19	Fixing verified tiles in dados skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing	Sqm	5.150	1227.30	6321.00
20	Fixing Ceramic tiles in floors on 20mm thick bed of CM(1:4) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing	Sqm	7.031	1074.10	7552.00
21	Fixing ceramic tiles in dados skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and	Sqm	25.144	1244.50	31292.00

polishing				
-----------	--	--	--	--

Item Sl. No	Item Description	Unit	Quantity	Estimated Rate excluding GST)	Total Amount in Rs.
22	Painting two coats over one coat of priming to the new iron works including cost of paints and primer etc. complete	Sqm	44.199	213.80	9450.00
23	Supplying and Fixing of M.S. Grills, M.S.Doors, M.S. Gate etc including cost,conveyance of all materials and labour for fitting fixing etc.complete as per the instruction of Engineer-in-Charge	Sqm	902.40	80.00	72192.00
24	Cost of Display Board	Nos	1	3600.00	3600.00
	TOTAL				1492551.00

(RUPEES FOURTEENLAKH NINETY-TWO THOUSAND FIVE HUNDRED FIFTY-ONE)only

I M/S _____ Class _____ contractor

hereby quoted my % (Percentage) rate at _____

/ _____ % (percentage) Both figure& ward) excess over than /Less than/

Equal to the amount put to tender Rs.1492551/-(*RUPEES FOURTEEN LAKH NINETY-TWO THOUSAND FIVE HUNDRED FIFTY-ONE*)only

Note:- The contractor should not write anything exceptQuoting of percentages and in case anything else regarding tender rate mentioned, the tender is liable to rejection.

1. Strike out which is not applicable.
2. Percentage should be quoted up to 2(two) digit after the decimal point
3. If not strikeout ,it will be treated as excess.
4. Nos of correction:- 5. Nos of over writing:-
6. Nos of interpolation:-
7. Nos of Pages:-

Dist:- _____
State:- _____
PIN: _____
Mobile No. _____

Signature of the contractor